

STANDARD WORK UNITS FOR LICENSEE BILLING

DESCRIPTION	MAN-HRS PER UNIT	UNIT	MATERIAL COST
<u>STREET LIGHTS</u>			
Remove Slack in Street Light Service	0.80	Service	0.00
Install Molding	1.10	Piece	0.00
Remove Molding	1.00	Piece	0.00
<u>SECONDARY</u>			
Raise Secondary Rack	0.90	Each	0.00
Raise Secondary Dead End	1.50	Leg	0.00
Raise Secondary Wire	0.80	Leg	0.00
<u>SERVICE</u>			
Raise Service	0.80	Service	0.00
Piece Out/Remove Slack in Service 1/0 or Smaller	1.80	Service	0.00
Remove Service	0.60	Service	0.00
<u>AERIAL CABLE</u>			
Transfer Riser Primary	1.40	Each	0.00
Transfer Riser Secondary/Service	1.40	Each	0.00
Install Cross Arm	0.70	Each	38.00
Remove Cross Arm	0.60	Each	0.00
Install Secondary Rack	0.60	Each	0.00
Remove Secondary Rack	0.50	Each	0.00
Install Pole Top Pin	0.60	Each	
Remove Pole Top Pin	0.50	Each	0.00
Install Primary Dead End Equipment 4kv	0.50	Phase	
Install Primary Dead End Equipment 13, 27 and 33kv	0.50	Phase	
Install Lightning Arrestor 4 and 13.2kv (3)	2.60	Phase	232.00
Install Lightning Arrestor 33kv (3)	2.60	Phase	462.00
Install Fused Cutout 13kv	1.20	Phase	121.00
Install Fused Cutout 33 kv	1.20	Phase	410.00
Install Ground Wire & Molding	0.80	Each	40.00
<u>PRIMARY</u>			
Raise Primary Cross Arm & Conductors	3.80	Each	38.00
Piece Out or Remove Slack in Primary 1/0	0.80	Phase	0.00
<u>REPLACE POLE</u>			
Install 35' Pole	3.50	Pole	293.00
Install 40' Pole	3.50	Pole	467.00
Install 45' Pole	3.50	Pole	556.00
Install 50' Pole	3.50	Pole	691.00
Remove Pole	2.10	Pole	0.00
Transfer Service	1.00	Service	0.00
Install Anchor Guy	2.00	Guy	105.00
Remove Anchor Guy	1.30	Guy	0.00
Transfer Anchor Guy	1.20	Guy	0.00
Install Transformer 1 Phase 13, 27 & 33 kv	2.20	Each	283.00

** Additional work may be required depending on the scope of the job*